Hampton Roads Regional Special Inspection Guidelines and Procedures 2018 USBC Edition



Revised: July 1, 2021

Participating Localities:

Accomack
Cape Charles
Chesapeake
Chincoteague
Franklin
Hampton
Isle of Wight
James City County
Newport News

Norfolk
Northampton
Poquoson
Portsmouth
Suffolk
Southampton
Virginia Beach
Williamsburg
York County

ACKNOWLEDGMENTS

The participating localities express our appreciation for the valuable assistance of all of the individuals and organizations who contributed to the creation of and revisions to *Hampton Roads Regional Special Inspection Guidelines and Procedures*. The most recent committee included the following members:

Steven I. Shapiro, CBO Deputy Director of Community Development (Retired) City of Hampton 22 Lincoln Street Hampton, Virginia 23669 (757) 727-6246 sshapiro@hampton.gov	Thomas W. Coghill, CBO Director Building Safety & Permits Division James City County 101-E Mounts Bay Road P.O. Box 8784 Williamsburg, VA 23187 (757) 253-6821 tcoghill@james-city.va.us (Procedure Coordinator)	Michael A. Matthews, P.E. President and CEO The Structures Group, Inc. 1200 Old Colony Lane Williamsburg, Va. 23185 (757) 220-0465 mmatthews@thestructuresgroup.com
William (Bill) Johnson, P.E. (Retired) TAM Consultants (Terracon) 4350 New Town Ave., Suite 203 Williamsburg, VA 23188 (757) 564-4434 bjohnson@tamconsultants.com	Michael J. Galli, P.E., D.GE South Region Manager Sr. Vice President ECS Mid-Atlantic, LLC 1643 Merrimac Trail, Suite A Williamsburg, Virginia 23185 (757) 229-6677 mgalli@ecslimited.com	Scott L. VanVoorhees, AIA Vice President Guernsey Tingle Architects 4350 New Town Avenue, Suite 101 Williamsburg, Virginia 23188 (757) 220-0220 slvanvoorhees@guernseytingle.com
Phillip Williams Building Commissioner Building Safety Department City of Norfolk 810 Union Street, Suite 508 Norfolk, Virginia 23510 (757) 633-7274 phillip.williams@norfolk.gov	Douglas K. Smith Director of Permits & Inspections Department City of Portsmouth 801 Crawford Street, 4th Floor Portsmouth, Virginia 23704 (757) 393-8531 doug.smith@portsmouthva.gov	

Legacy members who were a	contributing part of previous for	mulations of this document
John Catlett, MCP	Roland McPherson, P.E.	Paul W. Burch, P.E
Code Enforcement Director (Retired)	President (Retired)	Senior Engineer, Quality Assurance,
City of Alexandria	McPherson, Broyles & Associates, P.C.	McKinney and Company
315 King Street, Suite 4200	6371 Center Drive, Suite 100	100 South Railroad Ave.
Alexandria, Virginia 22314	Norfolk, Virginia 23502	Ashland, Virginia 23005
(703) 838-4360	(757) 965-2000	(804) 798-1451
John.catlett@alexandriava.gov	rncpherson@mbaeng.com	pburch@mckinney-usa.com
James H. Baldridge, P.E.	Sheldon J. Leavitt, AIA, P.E.	Douglas H. Murrow, AIA, CBO
President (Retired)	Leavitt Associates (Retired)	Building Commissioner (Retired)
Engineering Consulting Services, Ltd.	4400 Colley Ave	City of Richmond Planning and
108 Ingram Road, Suite 1	Norfolk, Virginia 23508	Development Review
Williamsburg, Virginia	(757) 489-7830	900 E. Broad Street
(757) 229-6677	sjl@leavittassoc.com	Richmond, Virginia 23219
jbaldridge@ecslimited.com		(804) 646-7000
Steven S. Welton, P.E.	Richard T. Stack	John Hopke
President,	Principal (Retired)	Principal in Charge
Welton Structural Design, P.C.	McPherson, Broyles & Associates, P.C.	Hopke & Associates
1901 Governor's Pointe Drive	6371 Center Drive, Suite 100	1156 Jamestown Road, Suite C
Suite B	Norfolk, Virginia 23502	Williamsburg, VA 23185
Suffolk, Virginia 23436	(757) 965-2000	(757) 229-1100
(757)238-2009	rstack@mbaeng.com	John.hopke@hopke.com
swelton@weltonsd.com		<u></u>
Hereld W "De" Debannen Jr. D.C. CDO	Mott Marshall Jr D.C	For H. Ingo. Ir. D.F.
Harold W. "Bo" Bohannon, Jr., P.E., CBO Project Engineer (Retired)	Matt Marshall, Jr, P.E. Vice President	Earl H. Inge Jr, P.E. Principal
The Structures Group, Inc.	Speight Marshall & Francis	Stroud Pence & Associates
1200 Old Colony Lane	2125 McComas Way Suite 103	5032 Rouse Drive
Williamsburg, VA 23185	Virginia Beach, Virginia 23456	Suite 200
villariosary, vi 20100	(757) 427-1020	Virginia Beach, Virginia 23462
	mjm@smandf.com	(757) 671-8626
	<u></u>	earl.inge@stroudpence.com
Lynn Underwood, CBO	Chuck Sutton, CBO, MCP	Andrew Bankowski
Code Official (Retired)	Inspections Coordinator	Plans Examiner
City of Norfolk	City of Virginia Beach	City of Virginia Beach
400 Granby Street	2405 Courthouse Dr., Bldg. 2	2405 Courthouse Dr. Bldg 2
Norfolk, Virginia 23510	Va. Beach, Virginia 23456	Virginia Beach, Virginia 23456
(757) 644-6899	(757) 385-4211	(757) 385-4211
lynn.underwood@norfolk.gov	cwsutton@vbgov.com	abankows@vbgov.com
Pat M. Hughes, CBO	C. Craig Hudson, AIA (Retired)	
Plan Review and Codes Administrator	Hudson + Associates Architects, PLLC	
Development and Permits	120 W. Queensway, Suite 201	
City of Chesapeake	Hampton, VA 23669	
P. O. Box 15225	(757) 722-1964	
Chesapeake, Virginia 23328	chudson@hudsonarch.com	
(757) 382-6018 phughes@cityofchesapeake.net		
priugries@dityordiesapeake.net		

TABLE OF CONTENTS

-	Pretace	Page 4
1.	Introduction	Page 5
2.	Definitions	Page 6
3.	Responsibilities	Page 9
4.	When Special Inspections are Required	Page 10
5.	Special Inspection of Fabricated Items	Page 10
6.	Special Cases	Page 11
7.	Special Inspector/Materials & Laboratory Testing Qualifications	Page 11
8.	Completing the Statement of Special Inspections (SSI)	Page 11
9.	Pre-Construction Meeting	Page 12
10.	Reports of Special Inspections	Page 13
11.	Final Report of Special Inspections	Page 14
12.	Changes in Design, Construction, and Special Inspection Personnel	Page 14
13.	Referenced Documents	Page 14
14.	Revisions to this Document	Page 15
15.	Appendices	
	A. Statement/Schedule/Final Report of S. I. B. Chart A	Pages 16-21 Page 22

Preface

As noted in the BOCA International manual **Designing a Special Inspection Program**,

"The effects of structural failures are far too many to list. The seriousness of such events gained the attention of the U.S. government. In August of 1982, a Subcommittee, chaired by Albert Gore, Jr., held investigative hearings to examine the causes of structural failure and find common problems associated with these conditions. The Subcommittee's ultimate goal was to eliminate those problems; thereby, decreasing the number of failures." (BOCA, P. 2)

To accomplish this goal, the Hampton Roads building safety community has joined together to formulate a uniform set of procedures for the manner in which participating jurisdictions enforce Special Inspection provisions of the Virginia Uniform Statewide Building Code (USBC). The provisions for Special Inspections are intended to provide a higher degree of expertise in the implementation of the structural design for critical aspects of building construction not normally found in the local building department.

The USBC is comprised of three (3) parts, of which Parts I and II are mandatory by the Commonwealth for each locality, while Part III is allowed to be optional per each locality's ordinances. Each part of the USBC incorporates and amends various International Code Council (ICC) codes as its basis. Specifically, Part I of the USBC, titled the Virginia Construction Code (VCC), adopts and amends the International Building Code (IBC) as well as the International Residential Code (IRC), Part II of the USBC, titled the Virginia Existing Building Code (VEBC), adopts and amends the International Existing Building Code (IEBC), and Part III of the USBC, titled the Virginia Maintenance Code (VMC), adopts and amends the International Maintenance Code.

The 2018 USBC adopted by the Code of Virginia on July 1, 2021 incorporates and amends the IBC. Please note all referenced code sections have been made to include any amendments to the IBC made by the VUSBC. The *Hampton Roads Regional Special Inspection Guidelines and Procedures* provides and coordinates the procedures for Special Inspections that are required by both the referenced USBC and IBC. These procedures and guidelines are intended to be useable during the design and permitting process and on the job site by containing the pertinent information needed for successful application of a Special Inspection program.

The Hampton Roads Regional Special Inspection Guidelines and Procedures includes the following:

- The responsibilities of the Registered Design Professional responsible for the structural design;
- The role of each member of the building construction team to include the Registered Design Professionals, Building Owner, Contractors, the Special Inspectors and Agents, and local Building Official;
- The experience and qualifications necessary to supervise and perform Special Inspections;
- Identification of the required areas of Special Inspections, and;
- Administrative procedures that include a uniform Special Inspection form that is accepted by the participating localities, important definitions, reporting requirements, and conflict resolution procedures.

The purpose of the *Hampton Roads Regional Special Inspection Guidelines and Procedures* is to increase awareness of the Special Inspection requirements and to have a uniform procedure applicable throughout the participating Hampton Roads communities. In addition, the uniform procedure should help reduce problems associated with permitting and performing Special Inspections in participating localities. Should you have any questions or suggestions for future editions of this document, contact the Procedure Coordinator noted on page 1.

1. Introduction

A. Purpose

The provisions for Special Inspections are intended to provide a higher degree of scrutiny for aspects of construction that, upon failure, would cause significant harm. These aspects of construction include soil suitability analysis, fabrication and installation of structural steel members, cold-formed steel members and decking, certain concrete and masonry construction, fabrication and installation of wood structural elements, pile and pier foundations, sprayed fire-resistant materials, wall panels and veneer systems, EIFS, special cases, and smoke control systems as detailed in the International Building Code (IBC).

The IBC as adopted by reference through the Virginia Uniform Statewide Building Code (USBC) intends that a Registered Design Professional be in responsible charge of the inspection of these special types of construction. The Hampton Roads building safety community has joined together in agreement to implement a uniform procedure for the manner in which jurisdictions enforce the Special Inspection requirements of the USBC and the IBC. This uniform procedure includes the standard for experience and qualifications necessary to adequately control the work being performed, duties of the Special Inspector, reporting requirements, as well as oversight by each jurisdiction. It specifies the type and manner of work and how it is to be performed and supervision required. It also clarifies the requirements for reporting the results and record keeping.

This uniform procedure is intended to safeguard public safety and general welfare through structural strength of building materials by:

- Clearly defining the responsibility of all parties involved in the Special Inspection process;
- Standardizing the necessary qualifications required for Special Inspectors (SI), as well as material testing and laboratories;
- Applying the Special Inspection provisions of the USBC in a consistent manner across the Hampton Roads Community.

B. Background

Numerous structural failures occurred during the late 1970's and early 1980's throughout the United States. These failures resulted in personal tragedies and tremendous property damage costs. However, most if not all of these failures were predicable in nature and centered on one common theme; lack of an adequate construction inspection process.

In August of 1982, the U.S. House of Representatives, Subcommittee on Investigations and Oversight, chaired by Albert Gore, Jr., held investigative hearings to examine the causes of structural failures. This subcommittee was part of the Committee on Science and Technology. In March of 1984, the Committee on Science and Technology's report titled *Structural Failures in Public Facilities*, House Report 98-621, was presented to the 98th Congress. The following are highlights from this report.

The central issue to be addressed by the Subcommittee was:

"Are there common problems associated with structural failures, the elimination of which would decrease the number of failures?"

While the Subcommittee identified over twenty contributing factors, two common problems were felt to be the most critical:

- The need for improved organization on construction projects and better communication between participants.
- The need for construction inspection(s) by the Structural Engineer of Record (SER) during the construction of principal structural components.

The Subcommittee found that:

"For a variety of reasons, the structural engineer of record or his designee is often not present on the job site during the construction of principal structural components. The absence of the structural engineer has permitted flaws and changes on site to go unnoticed and uncorrected."

The Subcommittee recommended that:

"Professional organizations, such as the Building Officials and Code Administrators International (BOCA), the International Conference and Building Officials (ICBO), and the Southern Building Code Congress International, (SBBCI) should make every effort to ensure that provisions are written into the building codes and adopted in public forum which make the on-site presence of the structural engineer mandatory during the construction of structural components on public facilities."

Model code organizations and Building Officials have attempted to address structural failures by enacting and enforcing Special Inspection provisions since 1987. However, the model codes have fallen short of requiring the Structural Engineer of Record (SER) to serve as the SI.

As time has elapsed and memories fade, Special Inspections and the role of the Structural Engineer of Record in this process have been topics of controversy and confusion in recent years. Many organizations, such as the American Council of Engineering Companies (ACEC) and the Virginia Structural Engineers Council (VSEC) as well as the Council of American Structural Engineers (CASE), agree with the Subcommittee's recommendations and believe strongly that the Structural Engineer of Record or his Designee (Agent) should serve as the SI whenever possible and practical.

2. Definitions

Words used in this procedure shall have a meaning as defined in the USBC and the IBC. Unless otherwise expressly stated, other words and terms shall have the meaning shown in this procedure. Where terms are not defined through the methods authorized by this section, such terms shall have ordinarily accepted meanings such as the context implies.

Agents of Special Inspector (Agents). Qualified individuals or agencies working under the direction of the SIs who are providing the inspections and tests necessary to complete the Special Inspection process.

Approved. See VCC Chapter 2

Approved agency. See VCC Chapter 2

Approved documents. Includes building construction documents approved by the municipality including all approved revisions and also fabrication and erection documents approved by municipality including all approved revisions.

Approved fabricator. See VCC Chapter 2, 1704.2.5.1

Architect of Record (AR). The Registered Design Professional (RDP) retained by the Owner to design or specify architectural construction in accordance with the USBC and whose signature and seal appears on the approved architectural construction documents.

Building. See VCC Chapter 2

Building Official. The local government authority charged with the administration and enforcement of the USBC. This shall include any duly authorized technical assistant as specified in the USBC See VCC Chapter 2

Certificate of Compliance. See VCC Chapter 2, 1704.2.5.1

Construction documents. See VCC Chapter 2

Contractor: A General Contractor licensed in the Commonwealth of Virginia (See Commonwealth of Virginia, Title 54.1)

Fabricated item. See VCC Chapter 2

Fabrication and erection documents. All of the written, graphic, and pictorial documents prepared or assembled after issuance of a building permit and in addition to the municipality approved construction documents, describing the design, location, and physical characteristics of the building components or materials necessary for fabrication, assembly, or erection of the elements of the project. (Examples would include, but are not limited to, concrete reinforcing shop drawings, steel fabrication and erection shop drawings, and metal building fabrication and erection shop drawings.)

Final Report of Special Inspections. A certification by the SI which shall indicate that all construction elements subject to Special Inspections as identified by the jurisdiction approved Statement and Schedule of Special Inspections (SSI) for all materials or phases of construction have been inspected prior to concealment, and in the SI's professional opinion and knowledge, the construction project complies with jurisdiction's approved Construction Documents.

Geotechnical Engineer of Record (GER). The Registered Design Professional (RDP) retained by the Owner to design or specify earthwork and foundations in accordance with the USBC, and whose seal and signature appear on the jurisdiction approved geotechnical report.

IBC. International Building Code as adopted and amended by the VCC

Independence. See VCC 1703.1.1

Inspection. The continuous or periodic observation of work and the performance of tests for certain building or structural components by the locality and/or third party to establish conformance with jurisdiction approved documents as required by the USBC and the IBC.

Inspection and testing agency. An established and recognized agency or agencies, meeting the requirements of ASTM E329 or approved equivalent and accredited, retained by the Owner, independent of the Contractors performing the work subject to Special Inspections, to perform Special Inspections and materials testing required by the USBC and the IBC. See VCC 1703.1 approved agency.

Inspection Certificate. An identification applied on a product by an approved agency containing the name of manufacturer, the function and performance characteristics, and the name and identification of an approved agency that indicates that the product or material has been inspected and evaluated by an approved agency. See VCC 113.5.

Owner. See VCC Chapter 2

Personnel. See VCC 1703.1.3

Pre-engineered structural elements. Structural elements specified by the SER but which may be designed by a Specialty RDP. (Examples are items such as open web steel joists and joist girders; wood trusses; combination wood, metal and plywood joists; pre-cast concrete elements; prefabricated wood or metal buildings; tilt-up concrete panel reinforcement and lifting hardware.)

Primary Registered Design Professional of Record (PRDP). The leader of the design team charged with the preparation of construction documents, either an architect or professional engineer. The PRDP is responsible for determining and interpreting the needs of the client or for coordinating the work of the other members of the design team.

Primary structural system. The combination of elements which serve to laterally brace and support the weight of the building's structural shell, the applicable live loads based upon use and occupancy, wind, snow, ice, thermal and seismic environmental loads.

Registered Design Professional (RDP). See VCC Chapter 2

Registered Design Professional in Responsible Charge. An architect or professional engineer, licensed to practice architecture or engineering, in direct control or supervision. Section 54.1-400 of the Code of Virginia

Risk Category. See VCC Chapter 2, 1604.5

Shall. This term indicates mandatory requirements.

Special Inspection, yes (Y), continuous (C), periodic (P), and not required (N). See VCC Chapter 2, 1704.2

Special Inspector (SI). The SI is the Registered Design Professional in Responsible Charge who is directly responsible for Special Inspections, materials testing, and related services as described in the approved SSI. The SI shall be retained by the Owner, independent of the Contractors performing the work subject to special inspection. The SI must be approved by the Building Official. The SI shall be listed as Agent 1 on the SSI. See VCC Chapter 2.

Sprayed fire-resistant materials. See VCC Chapter 2, 1702.1

Statement of Special Inspections (SSI). The SSI is a statement prepared by an RDP and shall be approved by the appropriate RDP(s) of Record and submitted by the permit applicant. The SSI includes the scope (schedule) of the Special Inspection services applicable to a construction project, and the RDP's and inspection and testing agencies that will provide those services. **The SSI is required as a condition for permit issuance in accordance with the VCC and must be approved by the Building Official.** See VCC 1704.2.3.

Structural Engineer of Record (SER). The Registered Design Professional retained by the Owner to design or specify structural documents in accordance with the VCC, and whose signature and seal appear on the jurisdiction approved structural construction documents.

Structural observation. See VCC Chapter 2, 1704.6

Structure. See VCC Chapter 2

USBC. The adopted Uniform Statewide Building Code in the Commonwealth of Virginia and includes Parts I, II, and III.

VCC. Virginia Construction Code, Part I of the USBC which adopts and amends the IBC.

3. Responsibilities

The **Building Official** is responsible for the issuance of the Building Permit and the Certificate of Occupancy. Prior to issuing the Building Permit, the Building Official will review and approve the Construction Documents, the SSI, and the qualifications of the SI and the Agents. Such qualifications of SI and agents must be submitted by resume to the Building Official for approval prior to issuance of the Building Permit. The Building Official shall review field reports of Special Inspections as directed by these guidelines and procedures. The Building Official has the authority to issue a stop work order if it is found that the approved Special Inspectors or Materials Testing Laboratories are not being utilized to perform required Special Inspections. The Certificate of Occupancy or final inspection shall be issued only after the Building Official has received and approved the Final Report of Special Inspections.

The **Contractor** is responsible for the construction of the project in accordance with the approved Construction Documents and the USBC. In addition, the Contractor is responsible for controlling the quality of construction and for providing the SI and Agents safe access to the elements that require inspection or testing. The Contractor shall coordinate construction related activities, including scheduling and timely notification of the need for Special Inspections and shall cooperate with the project's design professionals, including the SI and Agents. The Contractor shall make the site available for inspections as necessary and shall deliver samples for testing when needed. The Contractor shall respond promptly when informed of nonconforming work. The Special Inspection process does not relieve the Contractor of responsibility for quality control.

The **Owner** shall be responsible for the fees and costs related to the performance of Special Inspection services. The Owner or their authorized agent shall sign the SSI.

The **Primary Registered Design Professional of Record (PRDP)** shall be responsible for informing the Owner of the need to provide for Special Inspections and for assisting the Owner as may be needed to retain the services of an RDP to provide SI services. The selected RDP shall complete a SSI that shall include the SI and all Agent(s). The RDP shall also review and act upon conditions noted in interim special inspection reports. The RDP shall also be responsible for supplying the SI with the necessary copies of current appropriate Construction Documents and approved submittals, fabrication, and erection documents, including those revisions and change orders affecting work to be inspected or tested.

The **Special Inspector (SI)** shall be a Registered Design Professional in Responsible Charge for performing, documenting, managing, and coordinating the Special Inspections and the efforts of the various Agents. Individual Agents may be retained by the Owner or by the SI, but they are responsible to the SI. The SI and agents shall be independent of the Contractors performing the work subject to Special Inspections. The Agents who are responsible for conducting inspections or tests shall be identified in the SSI that is submitted to the Building Official. The SI shall provide copies of inspection reports to the RDP of Record, Owner, Contractor and Building Official. All discrepancies shall be brought to the attention of the Contractor for correction. The SI shall report deviations from the approved Construction Documents to the appropriate RDP of Record for their resolution. Uncorrected work shall be reported to the Building Official and the appropriate RDP of Record.

The **Structural Engineer of Record (SER)** shall be responsible for identifying in the Construction Documents the specific structural Special Inspections to be performed for the project in order to meet the requirements of the USBC and any other requirements specified by the SER. Approval of substitutions/discrepancies/ deviations from the approved Construction Documents must be provided to the Building Official by the SER with a signed and sealed document.

4. When Special Inspections are Required

In accordance with Section 111.2 of the VCC, Special Inspections shall be made in accordance with the requirements of Chapter 17. The requirements for Special Inspections shall be determined prior to and are requisite for issuance of the building permit.

Special Inspections are required for building and structural components identified in the VCC when the design of these components is required to be performed by a professional engineer or architect. VCC 111.1 notes information on the types of construction required to be designed by an RDP is included in the "Related Laws Package". CHART A from the "Related Laws Package" which summarizes § 54.1 – 402 of the Code of Virginia is attached.

The Building Official shall be permitted to waive Special Inspections and tests (VCC 1704.2). Additionally, unless otherwise required by the Building Official, Special Inspections and tests are not required for the following:

- One (1) story buildings under 20 feet in height which do not exceed 5,000 square feet in building area (VCC 1704.2); or
- Alterations to Group U structures which do not increase loads in accordance with Sections 603.7.3 and 603.7.4 of the VEBC (VCC 1704.2).
- Occupancies in Groups R-3, R-4 or R-5 and occupancies in Group U that are accessory to a residential occupancy (VCC 1704.2).
- Portions of structures designed and constructed in accordance with the cold-formed steel light-frame construction provisions of Section 2211.1.2 of the VCC or the conventional light-frame construction portions of Section 2308 of the VCC (VCC 1704.2).

Note: Check the requirements for each component of a building or structure listed in VCC Chapter 17 to determine if the exceptions to the requirement for Special Inspections of that component are applicable.

5. Special Inspection of Fabricated Items

Where fabrication of structural, load-bearing, or lateral load-resisting members or assemblies is being conducted on the premises of a fabricator's shop, *Special Inspections* of the *fabricated items* shall be performed during fabrication. The *SI* shall be required to review and verify that the fabricator maintains written procedural and quality control manuals, has the capability to fabricate the items in accordance with the *approved* drawings, standards, and specifications, and complies with the design details and the fabricator's quality control manual (VCC 1704.2.5).

Special Inspections during fabrication are not required where the work is done on the premises of a fabricator approved to perform such work without Special Inspection. Approval shall be based upon review of the fabricator's written procedural and quality control manuals and periodic auditing of fabrication practices by an approved agency. At completion of the fabrication, the approved fabricator shall submit a certificate of compliance stating that the work was performed in accordance with the approved construction documents (VCC 1704.2.5.1).

6. Special Cases

As per Section 1705.1.1 of the VCC, Special Inspections shall be required for proposed work that is, in the opinion of the Building Official or the RDP, unusual in its nature, such as but not limited to, the following examples:

- Construction materials and systems that are alternatives to materials and systems prescribed by the building code according to VCC 112.2.
- Unusual design applications of materials described in the building code.
- Materials and systems required to be installed in accordance with additional manufacturer's instructions that prescribe requirements not contained in the building code or in standards referenced by the building code.

7. Special Inspector/Materials & Laboratory Testing Qualifications

Special Inspections shall be performed by individuals and Agents that are qualified in accordance with these procedures and are under the direct supervision of an RDP in responsible charge of Special Inspection activities. The RDP shall ensure that the individuals under their charge are performing only those Special Inspections that are consistent with their knowledge and training for the specified inspections in accordance with the edition of ASTM E329 and the USBC that is in force at the time of permit issuance (VCC 1703.1).

The VCC requires that Special Inspections must be conducted under the supervision of an RDP. This places a requirement that the individual responsible for the coordination of Special Inspections (Agent 1) must be a Virginia licensed engineer or architect. Individuals or firms that conduct testing and/or Special Inspections (and the procedures they must follow) must comply with the requirements of ASTM E329. Firms providing Special Inspection services (or qualifications for individual inspectors) may submit documentation demonstrating equivalency by another recognized standard to the minimum qualifications, certification, and experience requirements of ASTM E329. The Building Official may approve the firm or individual after evaluating and determining that equivalency has been met (VCC 1703.1.3).

Individual resumes indicating pertinent training, certifications, and/or other qualifications shall be provided for Special Inspection personnel associated with the project. Written documentation shall also be provided to the Building Official demonstrating the applicable Agency's laboratory accreditation. Each local building department may prescribe the manner of qualification documentation and frequency of updating information regarding firm or individual inspector approval (VCC 1703.1.3).

8. Completing the Statement of Special Inspection (SSI)

A complete SSI shall be provided with the application for building permit. A complete SSI will contain the following:

- The Statement of Special Inspections form shall be completed to include signatures by the parties identified on the SSI to include:
 - A Registered Design Professional (RDP) is required to complete the Statement and Schedule of Special Inspections. Although not required, typically this is accomplished by a RDP associated with the project design and understanding the critical elements. This can be the Structural Engineer of Record (SER), SI or any other RDP knowledgeable of the project that can execute the form. Their name is typed/printed on the line "Type or print name of the preparer of the Schedule." The Virginia RDP seal and signature of the preparer is to be located above the printed name where indicated.

- The Applicant's signature is required if the person applying for the permit is different from the Owner. This can be the Owner's authorized representative, a RDP authorized by the Owner or the appropriately licensed Contractor that will be performing the work. The Applicant provides a signature on the "Permit Applicant's Signature" line. If the Applicant and Owner are the same and the Owner has signed on the "Owner's Authorization" line, a seperate signature is not required on this line.
- The project Owner's authorization is required as they are responsible for the fees and costs of the SI. By signing this form, they acknowledge that Special Inspections are required for the project and agree to notify the Building Official of any changes regarding the Special Inspection agents. The Owner provides a signature on the "Owner's Authorization" line.
- The PRDP of Record for the design provides a signature on the "Primary RDP of Record" line. The Primary RDP of Record is ususally the person with the most direct contact with the Owner. Typically, this would be the primary design professional that coordinated the completion of the plans. By signing, the Primary RDP of Record is not taking on a responsibility for the entire Special Inspection process nor approval of the Special Inspection team. The signature is an acknowledgement that Special Inspections are required on the job based on the design of his/her project, has advised the Owner of their responsibility to provide and pay for Special Inspections, and has assured that Special Inspections are properly called for in the schedule for areas dictated by his/her design are incorporated.
- The SER (if different from the PRDP of Record noted above) signs the SER line. The signature is an acknowledgement that the SER has reviewed the statement to ensure all required inspections dictated by his/her design are incorporated.
- The company name of the SI (Agent 1) is to be typed or printed on "Special Inspector" line. The RDP overseeing the implementation of Special Inspections for the project for the above named company will place his/her signature in the "Special Inspector (Signature)" line.
- The Building Official shall sign the form after all required signatures have been executed, he/she is satisfied that the area(s) of Special Inspections have been properly identified and called for, and he/she is satisfied that the Special Inspection agents and testing laboratories are properly qualified and certified. The signature of the Building Official shall signify acceptance and approval of the Statement/Schedule of Special Inspections.
- The Schedule of Special Inspections shall be included with proper identification of elements requiring Special Inspections continuous, periodic, and not required (C, P, N), as well as the associated Agent(s) responsible for inspection and/or testing.
- Agents for Special Inspections shall be identified to include address, phone number, and responsible party. (Agent 1, Agent 2, Laboratory, etc...) Agent 1 shall always be the primary SI responsible for the coordination of the entire Special Inspection process.
- Proper documentation as to appropriate qualifications and certifications as discussed in Section 7.

9. Pre-Construction Meeting

In accordance with the VCC Section 113.4, the Building Official may designate additional inspections to be conducted during construction. Additional inspections consisting of pre-construction meetings shall be

conducted by the SI at the start of the project or prior to the construction of the specific trade of work unless specifically waived by the Building Official. The meeting is to be attended by the following individuals:

- Special Inspector
- Special Inspection Agent(s)
- Contractor
- Subcontractor's representatives for each trade of work specified in the SSI

The following individuals are to be notified of the pre-construction meeting and are encouraged to attend whenever possible:

- Owner
- RDP(s) of Record for each scope of work specified in the SSI
- Building Official (or his/her designee)

The meeting should provide a forum to review and explain the following:

- Work to be reviewed as specified in the SSI.
- Inspections performed by the Building Official.
- Timely notification required by the Contractor to the SI of when the work is ready for inspections during the course of the work.
- Procedures to document, correct, re-inspect, and complete items found to be non-compliant or deficient.
- Identification of the RDP designated to resolve field deviations and non-compliant items if different from the RDPs responsible for preparing the construction documents.
- Contact information of individuals involved with the project.
- Discussion of the inspections and testing to be performed.
- Proper submission and distribution of reports and supplemental information.
- Discussion of coordination of all work to be performed in accordance with the Contract Documents and that no changes shall be permitted unless authorized and approved in writing by the RDP of Record for the work in question.
- Special Inspections of fabricated items are not required where the fabricator maintains approved detailed fabrication and quality control procedures and periodic inspection of fabrication and quality control procedures by the Building Official. (VCC 1704.2.5)
- Special Inspections of fabricated items are also not required where the work is performed on the
 premises of a fabricator registered and approved to perform such work based on a review of the
 fabricator's written quality control manuals and periodic auditing of fabrication practices by an
 approved agency. Upon completion of fabrication, a certificate of compliance must be submitted to
 the Owner or Owner's Agent for submittal to the Building Official stating such work was performed
 in accordance with the approved construction drawings. (1704.2.5.1)

A report shall be prepared by the SI indicating that the pre-construction meeting was conducted. The report shall indicate the date and location of the meeting, the attendees, and a brief description of the items discussed. A copy of the report shall be distributed as required in Section 10.

10. Reports of Special Inspections

The SI or agent shall provide a report for each inspection according to the standards of ASTM E329. The SI shall provide copies of inspection reports to the PRDP, SER, Owner, Contractor, and Building Official. The SI shall report deviations from the approved Construction Documents to the appropriate RDP for their resolution before proceeding with the inspection of the deficient work. All inspection and test reports including the pre-

construction meeting shall be submitted within seven (7) working days of the inspection, test performed, or meeting conducted. In no case shall inspections be performed by the Building Official that would allow the concealment of work required to be inspected by the SI unless verification has been received that the Special Inspection has been successfully performed.

Special Inspection and testing reports shall indicate that the specified work has been inspected and found to be in compliance with the approved construction documents unless deficiencies are noted. Reports containing deficiencies or non-compliant work shall describe the nature and specific location of the discrepancies.

At the completion of a project, all recorded non-compliant work shall be documented as having been corrected or approved by the RDP(s) of Record or other RDP(s) responsible for any review and approval of deviations or changes from the approved construction documents as appropriate.

Upon request of the Building Official, the SI shall submit a letter indicating completion of a specific area or phase of Special Inspections and testing for a particular construction discipline.

11. Final Report of Special Inspections

Upon completion of all Special Inspections and testing specified on the SSI, the SI shall, after review and approval by the appropriate RDP(s), submit a Final Report of Special Inspections, which includes the completed Schedule of Special Inspections, and if applicable, a Fabricator's Certificate of Compliance as required by VCC 1704.2.5.1 to the Building Official for review and approval. The Building Official's review and approval are required prior to final building inspection approval or issuance of a Certificate of Occupancy.

12. Changes in Design, Construction, and Special Inspection Personnel

In the event that the members of the Special Inspections Team or the organizations or individuals contracted as agents to the SIs are changed during the course of construction, the *Owner* shall provide a written notification for such change to the Building Official. Such notice shall identify the replacement organization or replacement individual and shall furnish the documentation necessary; including resume and experience to illustrate such organization or individual is qualified for the work required. The Building Official shall approve or deny such replacement. The *Owner* shall then provide a revised Statement of Special Inspections signed by all parties. A new pre-construction meeting with the Design Team, Construction Team, Special Inspection Team, and the replacement organization or a replacement individual must be provided. The *Owner* shall ensure that there is a timely transfer of information and responsibility to the replacement party.

13. Referenced Documents

- 2018 Edition of the Virginia Construction Code that adopts by reference and amends the 2018 Edition of the IBC published by the International Code Council.
- VCC Chapter 35, Referenced Standards
 - o ACI 318-14 Building Code Requirements for Structural Concrete.
 - AISC 360-16, Specification for Structural Steel Buildings.
 - o ASCE 7-16 Minimum Design Loads and Associated Criteria for Buildings and Other Structures.
 - ASTM E329-02, Standard Specification for Agencies Engaged in Construction Inspection and Testing.
 - o TMS 402/602-16 Building Code Requirements and Specifications for Masonry Structures.

14. Revisions to this Document (including Statement of Special Inspections)

This document is endorsed by the jurisdictions listed on the cover sheet. Revisions will be made from time to time by this group. The date of such revision will be provided on the cover as well as to the right of the page number at the bottom of all pages of this document. Any unauthorized revision may cause the document not to be accepted by the jurisdictions.

Appendix A

HAMPTON ROADS AREA STATEMENT OF SPECIAL INSPECTIONS

PROJECT	PERMIT APPLICANT
PRIMARY RDP OF RECORD	STRUCTURAL ENGINEER OF RECORD
Code (IBC) as stated in the Virginia Uniform Statewide Building C	on for permit issuance in accordance with the International Building ode (USBC). It includes a Schedule of Special Inspections applicable the identity of other testing laboratories or agencies intended to be
Registered Design Professional(s) (RDP(s)), Owner and Contract the Contractor for correction. If the discrepancies are not correct	It shall furnish inspection reports to the Building Official, appropriate stor. All discrepancies shall be brought to the immediate attention of sed, the discrepancies shall be brought to the attention of the Building itted to the Building Official, Owner, Contractor, and the appropriate stion Guidelines and Procedures.
equipment and methods used to erect or install the materials inspections shall be the responsibility of the Owner. Addition	rials and activities to be inspected are not to include the contractor's listed. All fees/costs related to the performance of Special nally, the undersigned (RDP or SER) are only acknowledging that are consistent with the required design elements, the applicable rea of expertise.
REVIEW, AUTHORIZATION & ACCEPTANCE: Permit Applicant (General Contractor): Signature / date:	SCHEDULE OF SI PREPARED BY:
Printed Name:	
Owner's Authorization: Signature / date:	
Printed Name:	
Primary RDP of Record:(Review and Acceptance of Schedule) Signature / date:	Virginia RDP Seal of SSI Preparer
Printed Name:	
SER of Record: (Review and Acceptance of Schedule) Signature / date:	Printed Name of the Preparer of the Schedule (on line above)
Printed Name:	Special Inspector:
Building Official's Acceptance:	Signature / date:
Signature / date:	Printed Name: SI Company Name:

SCHEDULE OF SPECIAL INSPECTIONS

MATERIAL /A CIPIANEN	TABLE OF INCIDENTIAN	APPLICABLE TO THIS PROJECT				
MATERIAL/ACTIVITY	TYPE OF INSPECTION	Y/C/P/N	EXTENT/REFERENCE	AGENT COMPLETED		
GENERAL						
Pre-construction conference	Meeting with parties listed in Section 9 of HRRSIGP to discuss Special Inspection procedures	•	Scheduled by SI with the Contractor prior to commencement of work; VCC 113.4			
EARTHWORK						
Site preparation (structure)	Field testing and inspection		Field Review; VCC 1705.6			
Fill material (structure)	Review submittals, field testing, and inspection		Field Review; VCC 1705.6			
Fill compaction (structure)	In-place density tests, lift thickness		Field Review; VCC 1705.6			
Excavation	Field inspection and verification of proper depth		Field Review; VCC 1705.6			
Foundation sub-grade (structure)	Field inspection of foundation subgrade prior to placement of concrete		Field Review; VCC 1705.6			
DEEP FOUNDATION/HELICAL PILE F	OUNDATION ELEMENTS					
Materials	Review product, sizes, and lengths		Submittal and Field Review; VCC 112.2, 1705.7, 1705.8, 1705.9			
Test piles	Monitor driving of test piles		Field Review; VCC 1705.7, 1704.8 or 1704.9			
Installation	Monitor drilling, placement, plumbness, driving of piles, including recording installation torque, pressure, blows per foot, cut off, and tip elevation		Field Review; VCC 1705.7, 1705.8, 1705.9			
Load test	Monitor pile load test		Field Review; VCC 1705.7, 1704.8 or 1704.9			
CONCRETE						
Materials	Review product supplied versus certificates of compliance and mix design		Submittal & Field Review; ACI 318: Ch. 19, 26.4.3, 26.4.4; VCC 1705.3, 1903.2, 1908.2, 1908.4			
Installation of reinforcing steel, including welding, as well as prestress tendons, anchor bolts, and fiber-reinforcement	Field inspection of placement		Submittal and Field Review; ACI 318: Ch. 20, 25.2, 25.3, 26.5.1-26.5.3; AWS D1.4; VCC 1705.3, 1705.3.1, 1705.3.2, 1901.3, 1908.4			
Formwork installation	Field inspection		Field Review; ACI 318; VCC 1705.3			
Concreting operations and placement	Field inspection of placement/sampling		Field Review; ACI 318: 26.5.2, 26.12.3; ASTM C 172, C 31; VCC 1705.3, 1908.6, 1908.7, 1908.8, 1908.10			
Concrete curing	Field inspection of curing process		Field Review; ACI 318: 26.5.3, 26.5.4; VCC 1705.3, 1908.9			
Concrete strength	Evaluation of concrete strength		Laboratory Testing; ACI 318: 26.12; VCC 1705.3			

MATERIAL /A CONTINUES	TABLE OF INCRECTION	APPLICABLE TO THIS PROJECT				
MATERIAL/ACTIVITY	TYPE OF INSPECTION		EXTENT/REFERENCE	AGENT COMPLETED		
Application of forces for prestressed concrete	Field inspection		Field Review; ACI 318: 26.10.2 (c); VCC 1705.3			
Grouting of prestress tendons	Field inspection		Field Review; ACI 318: 19.4.1, 20.6.4, 26.13.3.2(b); VCC 1705.3			
PRECAST CONCRETE						
Verify fabrication/quality control procedures	In-plant inspection of fabrication/quality control procedures**		Submittal or Field Review; VCC 1704.4.2.5, 1705.3			
Erection and installation	Review submittals and as-built assemblies; Field inspection of in-place precast		Submittal and Field Review; ACI 318; VCC Table 1705.3			
MASONRY (Level; Building Risk (Category)					
Materials	Review of products supplied versus certificate of compliance and material submitted		Submittal & Field Review; VCC 1705.4, 1709; TMS 402/602			
Strength	Testing/review of strength		Submittal & Field Review; VCC 1705.4, 2105; TMS 402/602			
Mortar and Grout	Inspection of proportioning and mixing. Placement of mortar only		Submittal & Field Review; VCC 1705.4; TMS 402/602			
Grout placement, including prestressing grout	Verification to ensure compliance		Field Review; VCC 1705.4; TMS 402/602			
Grout space	Verification to ensure compliance		Field Review; VCC 1705.4; TMS 402/602			
Mortar, grout, and prism specimens	Observe Preparation		Field Review; VCC 1705.4; TMS 402/602			
Reinforcement, prestressing tendons, and connections	Inspect condition, size, location, and spacing		Field Review; VCC 1705.4; TMS 402/602			
Welding of reinforcing bars	Inspection and testing of welds		Field Review; VCC 1705.3.1, 1705.4; TMS 402/602			
Prestressing force	Verify application and measurement		Field Review; VCC 1705.4; TMS 402/602			
Protection	Inspect procedures for protection during cold and hot weather		Field Review; VCC 1705.4; TMS 402/602			
Anchorage	Inspection of anchorages		Field Review; VCC 1705.4; TMS 402/602			
Masonry installation	Inspection of placement of masonry and joints		Field Review; VCC 1705.4; TMS 402/602			
STRUCTURAL STEEL						
Verify fabrication/quality control procedures	In-plant inspection of fabrication/quality control procedures** or submit Certificate of Compliance		Submittal or Field Review; VCC 113.5, 1704.2.5, 1704.2.5.1, 1705.2			
Bolts, nuts, and washers – materials	Material identification markings; Review of Certificate of Compliance		Submittal & Field Review; VCC 1705.2.1; AISC 360 Section A3.3			
Bolts, nuts, washers – installation	Inspection of in-place high-strength bolts, snug-tight joints, pre-tensioned and bearing type, and slip critical connections		Submittal & Field Review; VCC 1705.2.1, 2204.2; AISC 360 Section M2.5			
Structural steel – materials	Material identification markings and review of Certificate of Compliance		Submittal & Field Review; VCC 1705.2.1; ASTM A6, A568; AISC 360 Section A3.1			

MATERIAL /ACTIVITY	TWINE OF INCIDENTIAN		APPLICABLE TO THIS PROJECT				
MATERIAL/ACTIVITY	TYPE OF INSPECTION	Y/C/P/N	EXTENT/REFERENCE	AGENT	COMPLETED		
Structural steel details – installation	Inspection of member locations, structural details for bracing, connections, and stiffening		Submittal & Field Review; VCC 1705.2.1; AISC 360				
Open-web steel joists and joist girders – installation	Inspection of end connections and bridging		Submittal & Field Review; VCC 1705.2.3; SJI-100				
Weld filler materials and welder certification	Review of identification markings, certificate of compliance, and welder certifications		Submittal & Field Review; AISC 360 A3.5				
Welds	Inspection and testing of welds		Field Review; VCC 1705.2, 2204.1; AWS D1.1, D1.3				
Cold-formed metal deck – materials	Review of identification marking manufacturer's certified test results		Submittal & Field Review; VCC 1705.2.2				
Cold-formed metal deck – installation	Review laps and welds		Submittal & Field Review; VCC 1705.2.2; AWS D1.3; SDI				
Cold-formed light frame construction – welds	Review welding operation		Field Review; VCC 1705.11, 1705.11.2, 1705.11.3				
Cold form light frame construction wind resistance – screws	Review screw attachment bolting, anchoring hold downs, bracing, diaphragms, struts		Field Review; VCC 1705.11, 1705.11.2, 1705.11.3				
Cold-formed steel trusses spanning 60' or greater	Inspection of temporary and permanent restraints/bracing		Submittal & Field Review; VCC 1705.2.4				
WOOD							
Verify fabrication/quality control procedures	In-plant inspection of fabrication/quality control procedures** or submit Certificate of Compliance		Submittal or Field Review; VCC 1704.2.5, 1704.2.5.1, 1705.5				
Metal plate connected wood/metal trusses spanning 60' or more	Review approved submittal and installation of restraint/bracing		Submittal & Field Review; VCC 1704.2.5, 1704.2.5.1, 1705.5, 1705.5.2				
Joist Hangers – Materials/Installation	Review manufacturer's material and test standards		Field Review; ASTM D 1761				
High-Load Diaphragms - Installation	Review submittal and as-built assemblies; Inspection of sheathing, framing size, nail and staple diameter and length, number of fastener lines, and fastener spacing		Submittal & Field Review; VCC 1705.5, 1705.5.1				
Wood Shear Walls – installation	Review nailing, bolting, anchoring, fastening, diaphragms, struts, braces, and hold downs when fasteners are ≤ 4 " on center		Field Review; VCC 1705.11.1				

2018 USBC Edition

	TYPE OF INCRECTION	APPLICABLE TO THIS PROJECT			
MATERIAL/ACTIVITY	TYPE OF INSPECTION	Y/C/P/N	EXTENT/REFERENCE	AGENT	COMPLETED
MAIN WIND FORCE RESISTING SYST	EM				
Wind requirements	Review of the system components and installation for wood construction, cold-formed steel light frame construction, components, and cladding		ubmittal & Field Review; VCC 1609.2, 1704.6.3, 1705.11		
SEISMIC FORCE RESISTING SYSTEM	S				
Seismic requirements	Review of the designated seismic systems and seismic force resistance systems	S	Submittal & Field Review; VCC 1613, 1704.6.2, 1705.12, 1705.13; ASCE 7		
SMOKE CONTROL					
Special Inspection of smoke control systems	Leakage testing and recording of device location; pressure difference testing, flow measurement and detection, and control verification	Fi	feld Review; VCC 1705.18, 1705.18.1, 1705.18.2		
	L, FIRE RESISTANT PENETRATIONS; JOINTS			ATING	
Structural member surface conditions	Field review of surface conditions prior to application	A	AWCI 12-B; VCC 1705.14, 1705.14.1, 1705.14.2		
Application/thickness/density/bond strength	Field review of application operations, thickness, and density		ASTM E605; AWCI 12-B; VCC 1705.14.1, 1705.14.2, 1705.14.3, 1705.14.4, 1705.14.5, 1705.14.6		
Mastic & Intumescent Fire Resistant Coating	Field review of application operations and thickness		AWCI 12-B; VCC 1705.15		
EXTERIOR INSULATION AND FINISH	\ /				
Application	Field Review of application/installation		ASTM E2570; VCC 1407.6, 1705.16		
SPECIAL CASES					
Retaining Walls	Field review of installation of pre-manufactured structural components, drainage, and compaction		Field Review; VCC 113.4, 1705.1.1		
MEP Sprinkler system hangers/supports	Field review of placement and anchorage		Field Review; VCC 903.3.1.1, 1705.1.1; NFPA 13: 9.2		
Alternative Materials and Systems	As requested by Building Official, review system and installation		VCC 112.2, 112.3, 113.4, 1705.1.1		
INSPECTION AGENTS	FIRM		ADDRESS	TEI	LEPHONE
1. Special Inspector:					
2. Materials and Testing Laboratory:					
3. Special Inspector Smoke Control System:					
4. (Additional Agents)					

Note: * The Qualifications of the Special Inspector and Testing Laboratories are subject to the Approval of the Building Official.

^{**} Inspection of quality control procedures required only if fabricator is not regularly inspected by an Approved independent inspection agency. See Section 5.

^{***}For construction projects in seismic regions, the Schedule of Special Inspections shall be expanded to include Architectural, Mechanical, and Electric components, as well as Storage Racks and Isolation Systems. Items in VCC Section 1705.12

FINAL REPORT OF SPECIAL INSPECTIONS

PROJECT	PERMIT APPLICANT
PRIMARY RDP OF RECORD	STRUCTURAL ENGINEER OF RECORD
	<u> </u>
project, and itemized in the State completed. Attached to this final	nowledge, and belief, the Special Inspections required for this ement of Special Inspections submitted for permit, have been report are the Certificates of Compliance for shop fabricated ablies. (Include this statement only if applicable).
Interim reports submitted prior to to basis for, and are to be considered	this final report, and numbered to, form a d an integral part of this final report.
Respectfully submitted,	
Signature	
Date	
Type or Print Name (Agent 1)	

Seal of SI

Upon completion of all Special Inspections and testing, the SI shall submit a Final Report of Special Inspections to Building Official for review and approval. The Building Official review and approval is required prior to final building inspection approval or issuance of a Certificate of Occupancy.

A/E SEAL ON DRAWINGS

The following chart is for quick reference to determine whether § 54.1 - 402 of the Code of Virginia requires construction documents submitted to the local building department are to be prepared by an architect or engineer (A/E).

CHART A - GENERAL DESIGN

Construction documents for buildings or structures require A/E design as indicated below. Electrical installations and plumbing and mechanical systems are addresses separately in Charts B and C.

FLOOR ARI			AREA IN SQUAF	RE FEET	HEIGHT		
GROUP CLASSIFICATION	DESCRIPTION	Total net not exceeding 5,000	Total net exceeding 5,000, but not exceeding 15,000	Total net exceeding 15,000	Not exceeding three stories	Exceeding three stories	
А	ASSEMBLY (all except churches)	YES	YES	YES	YES	YES	
A-3	CHURCHES ONLY	Not if occupant load of 100 or less	YES	YES	Not if occupant load of 100 or less	YES	
В	BUSINESS	-	YES	YES	-	YES	
E	EDUCATIONAL	YES	YES	YES	YES	YES	
F	FACTORY AND INDUSTRIAL	-	-	YES	-	YES	
Н	HIGH HAZARD	YES	YES	YES	YES	YES	
I	INSTITUTIONAL	YES	YES	YES	YES	YES	
М	MERCANTILE	-	YES	YES	-	YES	
R-1	HOTELS, MOTELS, ETC.	YES	YES	YES	YES	YES	
R-2, R-3, R-4, AND R-5	RESIDENTIAL HOUSING, ETC.	-	-	-	-	YES	
S	STORAGE	-		YES		YES	
U	UTILITY & MISCELLANEOUS	SEE NOTE 6					

Notes:

- In accordance with § 54.1-410(A) of the Code of Virginia, officials of local building departments may require A/E design even if not required by state law.
- 2. Exempt construction documents must bear the name and address of the author and his or her occupation.
- 3. In accordance with § 54.1-402(B)(1) of the Code of Virginia, construction documents for any unique design of structural elements for floors, walls, roofs or foundations are required to have A/E design.
- 4. In accordance with § 54.1-402(A)(9) of the Code of Virginia, building or structures which are not otherwise exempted but which are of standard design are not required to have A/E design, provided they bear the certificate of a professional engineer or architect registered or licensed in another state, and provided that the design is adapted for the specific location and for conformity with local codes, ordinances, and regulations, and is so certified by a professional engineer or architect licensed in Virginia.
- 5. In accordance with § 54.1-402(A)(5) of the Code of Virginia, additions, remodeling or interior design without a change in occupancy or occupancy load and without modification to the structural system or a change in access or exit patterns or increase in fire hazard are not required to have A/E design.
- 6. Group U includes agricultural (farm) buildings and structures which are exempt from the Uniform Statewide Building Code (USBC). In addition, Group U retaining walls with less then three feet of unbalanced fill and fences do not require permits under the USBC. Other Group U structures such as bridges, towers, private garages, tanks, etc., may require A/E design at the discretion of the local building official.